APPENDIX D: WATER RESOURCES

D.1 Wetland and Waterbody Impact Table

Wetland and Waterbody Impact Table

| Existing Wetland | Existing (acres) | Proposed (acres) | Difference (acres) | Total Wetland Disturbance (acres) | Description |
|------------------|---|------------------|-----------------------|---|---|
| Wetland A* | 0.52 | 0.85 | 0.33 | 0.52 | Pond regraded and expanded for stormwater management |
| Wetland B | 0.87 | 0.89 | 0.02 | 0.87 | Pond regraded and expanded for stormwater management |
| Wetland D | 0.43 | 0.67 | 0.24 | 0.08 | Partially filled and expanded |
| Wetland G-1 | 0.33 | 0.33 | 0.00 | 0.02 | 0.02 AC regraded |
| Wetland H | 0.51 | 0.51 | 0.00 | 0 | Stone wall proposed along western edge |
| Wetland I* | 0.06 | 0.00 | -0.06 | 0.06 | Completely filled |
| Wetland J-1 | 0.44 | 0.48 | 0.03 | 0.139 | Pond reconfigured |
| Wetland K + Z | 2.06 + 5.53 | 8 | 0.72 | 0.133 | Expanded and connected Wetlands K + Z; stone wall proposed along western edge of Wetland K for golf grading |
| Wetland N | 0.15 | 0.59 | 0.44 | 0.026 | Partially filled and expanded for stormwater management |
| Wetland O | 0.03 | 0.00 | -0.03 | 0.03 | Completely filled |
| | | TOTALS | 1.69 | 1.878 | |
| excludes | TOTALS (Jurisdic s acreage of Isolated | · 1 | 1.42 | 1.298 | |

^{*} Wetlands A and I are isolated wetlands and are not included in the jurisdictional acreage - Refer to the "Silo Ridge Map of Wetland Survey Prepared for Higher Ground Country Club Management Co., LLC" dated 1/13/06 Rev. #5 dated 5/30/07.

| Existing Surface Waterbody | Existing (Linear Feet) | Proposed (Linear Feet) | Difference (Linear Feet) | Description | |
|-------------------------------|---------------------------|---------------------------|-----------------------------|--|--|
| Stream E-1 | 225 | 0 | -225 | Completely filled | |
| Stream E-2 | 260 | 60 | -200 | Partially filled | |
| Stream G | 198 | 385 | 187 | Completed filled; stream relocated as extension of Wetland G | |
| Stream J (Upper) | 288 | 288 | 0 | Approx 90 LF will be disturbed during construction to install culvert pipe | |
| Stream M/P | 434 | 404 | -30 | Partially filled and regraded 90 LF | |
| Stream O | 74 | 0 | -74 | Completely filled | |
| Stream QQ | 330 | 110 | -220 | Partially filled | |
| | | TOTAL | -562 | | |